

REPORT

Central Plains Water Enhancement Scheme:

Assessment of Environmental Effects for Resource Consent Applications to Canterbury Regional Council



Prepared for



Central Plains Water Trust



23 June 2006

42156547.66140 \ AEE R001C

URS

Project Manager:  URS New Zealand Limited
Walter Lewthwaite Level 5, Landsborough House
Environmental Engineer, Associate 287 Durham Street, Christchurch
PO Box 4479, Christchurch New Zealand
Project Director: 
Cliff Tipler Tel: 64 3 374 8500
Senior Principal Fax: 64 3 377 0655

Authors: Mark Mabin Date: **23 June 2006**
Senior Environmental Scientist Reference: 42156547\66140\R001C
Cliff Tipler Status: Amended final
Senior Principal
Walter Lewthwaite
Senior Environmental Engineer
Klaus Ohlbock
Water Resources Engineer
Daniel Murray
Environmental Planner
Matthew Gardner
Water Resources Engineer

Notice

This AEE has been updated since lodgement in November 2005 to reflect changes to details resulting from further consultation and refinement of design. The changes are primarily over location of canals. The details in this AEE are consistent with the Land Use Consent Applications and Notice of Designation Requirement lodged with Selwyn District Council in June 2006, and with the consent application Notification by Canterbury Regional Council of June 2006.

1	Introduction	1-1
1.1	Purpose of this Report	1-1
1.2	Central Plains Water Enhancement Scheme	1-1
1.3	Background	1-3
1.3.1	Central Plains Water Trust	1-3
1.3.2	Central Plains Water Limited	1-4
1.3.3	Future development of Central Plains Water Enhancement Scheme	1-4
1.3.4	Requiring Authority Status	1-4
1.4	Overview of Consents and Designations Required for this Scheme	1-5
1.4.1	Previous Resource Consent Applications Relating to this Scheme	1-5
1.4.2	Resource Consents Sought in this Application	1-6
1.4.3	Resource Consents and/or Designations Required from Selwyn District Council	1-15
1.5	Land Ownership	1-16
1.6	Report Structure	1-16
1.7	4 th Schedule	1-17
2	Central Plains Water Enhancement Scheme	2-1
2.1	Background	2-1
2.1.1	Irrigation Development in Canterbury	2-1
2.1.2	The need for agricultural development	2-2
2.1.3	The need for water in Canterbury	2-3
2.1.4	Early attempts to obtain water	2-4
2.2	Scenarios for the Central Plains	2-4
2.2.1	Business as Usual	2-4
2.2.2	Water Enhancement	2-5
2.3	Development of the Central Plains Water Enhancement Scheme	2-5
2.3.1	Scheme History	2-5
2.3.2	Steering Committee	2-6
2.3.3	Central Plains Water Trust	2-7
2.3.4	Central Plains Water Limited	2-7
2.4	Summary	2-8
3	Description of the Proposed Activities	3-1
3.1	Introduction	3-1
3.2	Scheme Area	3-1
3.3	Water Takes	3-2
3.3.1	Rakaia River takes	3-3
3.3.2	Waimakariri River takes	3-5
3.4	Intakes and Headworks	3-7
3.4.1	Rakaia River intake	3-7
3.4.2	Sediment removal works	3-9
3.4.3	Fish screens	3-10
3.4.4	Waimakariri River intake – lower site	3-10
3.4.5	Waimakariri River intake – upper site	3-12
3.5	Inlet Canal and Tunnel to Waianiwaniwa Reservoir	3-13
3.5.1	Canal route	3-14
3.5.2	Canal size	3-15
3.5.3	Canal crossings, cuttings, and traverses	3-16

Contents

3.5.4	Canal earthworks	3-17
3.5.5	Tunnel	3-17
3.6	Waianiwaniwa Dam	3-18
3.6.1	Embankment design	3-20
3.6.2	Construction materials	3-21
3.7	Reservoir	3-22
3.8	Reservoir Outlet	3-23
3.9	Headrace System	3-23
3.9.1	Headrace route	3-23
3.9.2	Canal size	3-24
3.9.3	Canal earthworks	3-24
3.9.4	Traverses	3-28
3.9.5	Siphons	3-28
3.9.6	Embankments	3-29
3.9.7	Cuttings	3-30
3.9.8	Other crossings	3-30
3.9.9	Outlet structures	3-33
3.10	Pump Stations	3-33
3.10.1	Coalgate pump station	3-34
3.10.2	Upper Waimakariri pump station	3-34
3.10.3	Lower Waimakariri pump station	3-34
3.10.4	Rakaia pump stations	3-34
3.11	Water Distribution Network	3-35
3.11.1	Springfield area	3-36
3.11.2	Sheffield Area	3-39
3.11.3	Darfield area	3-40
3.11.4	Greendale area	3-44
3.11.5	Coalgate area	3-44
3.11.6	Hororata area	3-46
3.11.7	Te Pirita area	3-46
3.11.8	Windwhistle area	3-49
3.12	Discharge points	3-51
3.12.1	Operational bywash discharge	3-52
3.12.2	Emergency peak flow discharge	3-54
3.12.3	From headrace	3-56
3.12.4	Release from Waianiwaniwa Reservoir	3-56
3.13	Construction Activities	3-56
3.13.1	Intakes and headworks structures	3-56
3.13.2	Waianiwaniwa Dam	3-58
3.13.3	Reservoir supply canal	3-61
3.13.4	Waianiwaniwa Reservoir Tunnel	3-61
3.13.5	Headrace	3-65
3.13.6	Distribution network	3-66
3.13.7	Siphons	3-66
3.13.8	Stream Crossings	3-67
3.13.9	Road and Railway Crossings	3-67
3.13.10	Heavy Machinery	3-68
3.13.11	Hours of Operation	3-68
3.13.12	Contractors' Work Sites	3-68
3.13.13	Construction Timetable	3-69
3.13.14	Health and Safety	3-69

3.14	Scheme Operation	3-69
3.14.1	Surface water takes	3-69
3.14.2	Stilling basins and sediment removal	3-70
3.14.3	Fish Screens	3-71
3.14.4	Reservoir filling and operations	3-71
3.14.5	Canal operation	3-72
3.14.6	Delivery of water to farms	3-72
3.14.7	Use of water on farms	3-73
3.14.8	Bywash	3-74
4	Consideration of Alternatives	4-1
4.1	Introduction	4-1
4.2	No further irrigation	4-1
4.3	Multiple small schemes	4-1
4.4	Major community owned scheme	4-2
4.5	Alternatives within proposed scheme	4-2
4.5.1	Alternative water sources	4-2
4.5.2	Alternative intakes	4-3
4.5.3	Alternative water storages	4-4
4.5.4	Alternative Distribution Systems	4-5
5	Consultation	5-1
6	Description of the Environment	6-1
6.1	Project Area	6-1
6.2	The Physical Environment	6-1
6.2.1	Waimakariri River	6-1
6.2.2	Rakaia River	6-4
6.2.3	Waianiwaniwa Catchment	6-7
6.2.4	Other Minor Rivers of the Foothills	6-8
6.2.5	Central Plains	6-10
6.2.6	Lowland Spring-fed Streams	6-12
6.2.7	Lake Ellesmere / Te Waihora	6-13
6.3	Groundwater Systems	6-14
6.3.1	General Hydrogeological Setting	6-15
6.3.2	Hydrogeological Characteristics	6-15
6.3.3	Hydrogeological Layers	6-16
6.3.4	Groundwater Level Data	6-18
6.3.5	Groundwater Table Trends	6-19
6.3.6	Groundwater Quality	6-19
6.3.7	Phosphorous	6-21
6.3.8	Other Constituents	6-21
6.4	Soil Environments of the Central Canterbury Plains	6-22
6.4.1	Soil Depth and Texture	6-22
6.4.2	Soil Moisture	6-23
6.4.3	Soil Drainage	6-25
6.5	The Climatic Environment	6-26
6.5.1	Rainfall	6-26
6.5.2	Evaporation	6-28
6.5.3	Water balance	6-28

6.5.4	Wind	6-29
6.5.5	Climate change	6-29
6.6	The Biological Environment	6-30
6.6.1	Terrestrial Ecology	6-30
6.6.2	In-stream Habitat	6-32
6.6.3	Water Quality	6-33
6.6.4	Algae, Macrophytes, and Invertebrates	6-35
6.7	Fish and Recreation	6-38
6.7.1	Fish Communities	6-38
6.7.2	Fishery Values	6-39
6.7.3	Recreational Values	6-39
6.8	The Social Environment	6-41
6.8.1	Profiles of the communities	6-41
6.8.2	Profiles of farmers	6-43
6.9	The Cultural Environment	6-44
6.9.1	Maori Cultural Environment	6-44
6.9.2	Historic Heritage	6-45
6.10	Landscape Values	6-46
6.10.1	Landscape Character	6-47
7	Assessment of Temporary Effects on the Environment	7-1
7.1	Introduction	7-1
7.2	Dust Effects	7-1
7.2.1	Water intakes	7-3
7.2.2	Headrace construction	7-3
7.2.3	Waianiwaniwa Dam site	7-3
7.2.4	Waianiwaniwa tunnel site	7-4
7.2.5	Distribution network	7-4
7.3	Noise	7-4
7.3.1	Water intakes	7-4
7.3.2	Headrace construction	7-5
7.3.3	Waianiwaniwa Dam site	7-5
7.3.4	Waianiwaniwa tunnel site	7-5
7.3.5	Distribution network	7-5
7.3.6	Noise summary	7-5
7.4	Construction Traffic Effects	7-6
7.4.1	Water intakes	7-6
7.4.2	Headrace construction	7-6
7.4.3	Waianiwaniwa Dam site	7-6
7.4.4	Waianiwaniwa tunnel site	7-7
7.4.5	Distribution network	7-7
7.4.6	Traffic summary	7-7
7.5	Effects on River Hydrology	7-7
7.5.1	Water intakes	7-7
7.5.2	Headrace construction	7-8
7.5.3	Waianiwaniwa Dam site	7-8
7.5.4	Waianiwaniwa tunnel site	7-8
7.5.5	Distribution network	7-8
7.5.6	Hydrology summary	7-8
7.6	Effects of sediment	7-9
7.6.1	Water intakes	7-9

7.6.2	Headrace construction	7-9
7.6.3	Waianiwaniwa Dam site	7-9
7.6.4	Waianiwaniwa tunnel site	7-10
7.6.5	Distribution network	7-10
7.6.6	Sediment discharge summary	7-10
7.7	Effects on water quality	7-10
7.7.1	Water intakes	7-11
7.7.2	Headrace construction	7-11
7.7.3	Waianiwaniwa Dam site	7-11
7.7.4	Waianiwaniwa tunnel site	7-11
7.7.5	Distribution network	7-11
7.7.6	Water quality summary	7-11
7.8	Effects on Aquatic biota	7-12
7.8.1	Water intakes	7-12
7.8.2	Headrace construction	7-12
7.8.3	Waianiwaniwa Dam site	7-12
7.8.4	Waianiwaniwa tunnel site	7-12
7.8.5	Distribution network	7-13
7.8.6	Aquatic biota summary	7-13
7.9	Effects on in-stream habitat	7-13
7.10	Effects on significant terrestrial and aquatic vegetation	7-13
7.11	Effects on birds and terrestrial fauna	7-14
7.12	Effects on fish and recreation	7-14
7.13	Effects on social and cultural values	7-14
8	Assessment of Effects of the Operation of the Scheme	8-1
8.1	Introduction	8-1
8.2	Effects of Diverting Water	8-1
8.3	Effects of Water Discharges	8-2
8.3.1	Sediment flushing	8-2
8.3.2	Fish Bypasses	8-3
8.3.3	Bywashes and Wetlands	8-3
8.4	Effects of Damming the Waianiwaniwa Valley	8-3
8.4.1	Introduction	8-3
8.4.2	Effects on Water Quality	8-4
8.4.3	Social Effects	8-12
8.5	Effects on Groundwater Systems	8-19
8.5.1	Overview of Data Sources	8-19
8.5.2	Assessment of Effects on the Groundwater from Changed land Use	8-26
8.5.3	Conclusions	8-34
8.6	Christchurch City Groundwater	8-35
8.6	Effects on Biological Environments	8-36
8.6.1	Terrestrial Ecology	8-36
8.6.2	Instream Habitats	8-37
8.6.3	Water Quality	8-38
8.6.4	Algae, Macrophytes, and Invertebrates	8-39
8.6.5	Fish and Recreation	8-39
8.7	Effects of Water Use on Soils	8-40
8.8	Effects on Landscape and Visual Amenity Values	8-41
8.8.1	Potential Effects	8-41
8.8.2	Visibility	8-43

8.8.3	Enhancement Measures	8-46
8.8.4	Conclusion	8-48
8.9	Effects on Tangata Whenua Values	8-48
8.10	Social Effects	8-50
8.10.1	Other effects	8-61
8.10.2	Conclusions	8-66
8.11	Economic Effects	8-67
8.11.1	Introduction	8-67
8.11.2	Agriculture and associated processing impacts	8-68
8.11.3	Scheme construction impacts	8-71
8.11.4	Combined construction, agriculture and processing impacts	8-71
8.12	Transportation Effects	8-72
8.12.1	Roading and Railway Hierarchy	8-73
8.12.2	Dam Area	8-73
8.12.3	Midland Railway Line	8-73
8.12.4	General Roading Network	8-73
8.12.5	Traffic Safety	8-75
8.12.6	Land Impacts at the Dam Site and Reservoir	8-76
8.12.7	Land Take and Revised Access Requirements	8-76
8.12.8	Specific Roading/Rail Issues	8-84
9	Mitigation, Monitoring and Conditions	9-1
9.1	Section 17 RMA	9-1
9.2	Avoiding adverse effects on the environment	9-1
9.2.1	Management Plans	9-1
9.2.2	Sustainable Farming	9-1
9.2.3	Ritso Society Irrigation Sustainability Code of Practice	9-2
9.3	Mitigating adverse effects on the environment	9-3
9.4	Remedying adverse effects on the environment	9-3
9.5	Proposed Monitoring	9-3
9.5.1	Water takes	9-4
9.5.2	Reservoir levels and water quality	9-4
9.5.3	Water distribution	9-4
9.5.4	Land application amounts	9-4
9.5.5	Bywash volumes	9-4
9.5.6	Wetland functioning	9-4
9.5.7	Groundwater levels	9-5
9.5.8	Groundwater quality	9-5
9.5.9	Environmental monitoring	9-5
9.6	Resource Consent Conditions	9-5
10	Statutory Framework	10-1
10.1	Introduction	10-1
10.2	Resource Management Act 1991	10-1
10.2.1	Part 2 – Purpose and Principles	10-1
10.2.2	Part 3 – Duties and Restrictions	10-4
10.3	Regional Policy Statement	10-6
10.4	Regional Plans	10-6
10.4.1	Activity Assessment	10-7
10.4.2	Waimakariri River Regional Plan – Objectives and Policies	10-7

Contents

10.4.3	Proposed Natural Resources Regional Plan – Objectives and Policies	10-10
10.5	District Plans	10-21
10.6	Other Legislation and Documents	10-22
10.6.1	Crown Minerals Act 1991	10-22
10.6.2	Ngai Tahu Claims Settlement Act 1998	10-22
10.6.3	Iwi Management Plans	10-22
10.6.4	Ngai Tahu Freshwater Policy	10-22
10.6.5	Rakaia River Water Conservation Order	10-23

Appendices

Appendix A	References	A-1
Appendix B	Locations and Maps.....	B-1
Appendix C	Memorandum of Agreement	C-1
Appendix D	Proposed Consent Conditions	D-1
Appendix E	Assessment of Regional Plan Rules	E-1